BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64
No:EE/YNK-D/E-PMT/04/2014-15 Dated: 31-10-2014

APPROVED TENDER SCHEDULE –'B'

Item No: 31

Name of Work:-Construction of Culverts in ward No-02 of yelahanka Sub division.

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri . S E RAJESH	
				Rate	Rate in Words
1	KSRB 2-2.1 : earth work excavation for foundation of buildings, culverts water supply, sanitary line and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods	Cum	90.00	170.75	Rupees one hundred seventy and paise seventy five only
2	KSRB 100-1 Loading and unloading ofstone aggregates / sand/ kanker/ Moorum /soil KSRRB M100-1 Placing tipper at loading with front end loader dumpting turning for return trip excluding time for haulged and return trip complete as per specification item No 17.1 page 130 and KSRB M.100.4.1 costof haulage excluding loading and unloading MORTH to a distance of 4.00 K.M (Item No 17.4 Page 130 (SR 2014-15)	Cum	90.00	76.72	Rupees seventy six and paise seventy two only
3	KSRB-4-1.2 : Providing and laying in position plain cement concrete of mix 1:3:6 withOPC cement at 220kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2, No. 12/ Item No. 4.2/ PWD SR 2014-15	Cum	13.50	4701.62	Rupees four thousand seven hundred one and paise sixty two only
4	KSRB 4.2.2 : Providing and laying in position plain cement concrete of mix M20 withOPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregates @0.460cum with superplastesisre @ 3lts conforming to IS9103-1999Reffirmed machine mixed exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, return walls, walls(any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc, including cost of all materials, labour HOM of machinery, curing, complete as per specifications. Specification. No. KBS 4.1,4.6, No. KBS 4.1,4.6, No. 13/ item No. 4.11/ PWD SR 2014-15	Cum	61.62	5863.32	Rupees five thousand eight hundred eighty three and paise thirty two only

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri . S E RAJESH	
				Rate	Rate in Words
5	KSRB 4.9.2:providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 Page No. 19/ Item No. 4.46/ PWD SR 2014-15	Qntl	54.08	7037.15	Rupeesd seven thousand thirty seven and paise fifteen only
6	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, attached pilasters,bittresses,buttresses plinth and string course including cost of all materials, labour complete as per specifications. Specification NO KBS 4.6.2 Page No. 15/ Item No. 4.31/ PWD SR 2014-15	Sqm	248.00	283.89	Rupeesd two hundred eighty three and paise eighty nine only
7	RCC Precast covering slab for drain (10cm thick)	Sqm	7.50	1453.06	Rupees one thousand four hundre fifty three and paise six only

S.E. Rajesh
Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.

ಮೊಬೈಲ್ ಸಂ:9985454545